

DREAMS MALL – HDD WORK - ADDITIONAL DETAILS

1. The selected contractor shall conduct site survey before commencement of work.
2. Necessary approvals shall be obtained from all agencies such as KSEB, NHAI, PWD, KWA, BSNL, all communication cable providers and other service providers/ agencies as required
3. Preparation of documents for submission to relevant departments/ organizations/ bodies/ service providers shall be done by the contractor. The documents will be signed by the DREAMS MALL management if mandates. All follow-ups, obtaining approvals etc. shall be done by the selected contractor
4. All statutory fees for getting approval shall be remitted by the contractor which will be reimbursed on production of original receipts.
5. The following are the approved make of materials:

Materials	Approved makes
11 kV XLPE insulated PVC sheathed aluminium conductor cable conforming to IS 7098 part 2	KEI, RR, Polycab, Gloster, Universal, CCI, AVO (Approved by KSEB/ CPWD/ KPWD/ ISRO etc)
Cable joints and terminations	Raychem, 3M
HDPE pipe shall be as per IS 4984:2016 reaffirmed in 2021 and match PE100, SDR11, DN110, PN0.80 specifications	Mangalam, Kodoor, Secure